



## CONSTRUCTION OF MJELWENI ACCESS ROAD IN WARD 12

CONTRACT No: NLM/MJAR/2020/2021

### ADDENDUM 1 TO TENDER

1. This Addendum shall form part of the contract.

Tenderers shall affix the additional and superseded pages attached to this document at the relevant sections in the tender document and insert this addendum behind Section Form G 'NOTICES TO TENDERS' of Part T2. Tenderers shall also record receipt of this addendum and return to the engineer.

2. Additions and/or Amendments to the following portions;

Part C2 – Section C2.2 – Bill of Quantities:

The following item, in the respective schedule, has been amended to clarify the description of that item or rectify incorrect quantities or specify the relevant payment reference:

Section No.	Item No(s)	Description of Amendment
1200	B12.02	Change in provisional sum
1200	B12.03	Change in provisional sum
2200	22.05 (b)(i)	Change in item description
3400	B34.01 (b)(ii)	Change in quantity

***Add and Replace additional plus superseded pages in the relevant sections of the tender document, with the new and corrected (amended) pages as depicted above.***

3. Confirmation of Receipt of Addendum

Tenderers are requested to confirm receipt of this addendum by completing the relevant information indicated below and returning a scanned copy, via email, to Msindisi Mashece at [mmashece@mbengineers.co.za](mailto:mmashece@mbengineers.co.za)

Name of tendering entity: .....

Contact Person: .....

Telephone No.: .....

Date: .....

Signature of Authorised Representative: .....

**END OF SECTION**

**ADDENDUM No. 1 to TENDER**

**Part C2 – Section C2.2 – Bill of Quantities:**

ITEM NO.	DESCRIPTION	UNIT	TENDER QTY	RATE	AMOUNT
	<b>1200 GENERAL REQUIREMENTS AND PROVISIONS</b>				
B12.01	Community Liaison Officers				
	(a) Community Liaison Officer cost	Prov. Sum	1.0	R 14 000.00	
	(b) Monthly transport allowance for CLO for duration of Contract	Prov. Sum	1.0	R 5 000.00	
	(c) Remuneration of PSC members to attend official meetings	Prov. Sum	1.0	R 6 000.00	
	(d) Handling costs and charges for Contractor on items B12.01 (a) to (c)	%	25 000.0		
B12.02	Protection or Relocate of Existing Services according to the Engineer's instruction	Prov Sum	1.0	R 50 000.00	
	(a) Handling costs and charges for the Contractor	%	R 50 000.00		
B12.03	Construction of name board according to specification	No	1.0		
B12.04	Environmental Control Monitoring	Prov Sum	1.0	R 135 000.00	
	(a) Handling costs and charges for the Contractor	%	R 135 000.00		
TOTAL CARRIED TO SUMMARY					

ITEM NO.	DESCRIPTION	UNIT	TENDER QTY	RATE	AMOUNT
	<b>2200 PREFABRICATED CULVERTS</b>				
22.01	Excavation				
	(a) Excavating soft material situated within the following depth ranges below the level surface level:				
	(i) 0m up to 1.5m	m³	70		
	(ii) Exceeding 1.5m up to 3m	m³	20		
	(b) Extra over sub item 22.01(a) for excavating in hard material, irrespective of depth	m³	36		
22.02	Backfilling:				
	(a) Using the excavated material	m³	35		
	(b) Using imported selected material	m³	20		
	(c) Extra over sub item 22.02(a) and (b) for soil cement backfilling	m³			
22.03	Concrete pipe culverts:				
	(c) On class C bedding				
	(i) 600mm dia class 100D	m	27		
	(ii) 900mm dia class 100D	m	3		
	(ii) 1.2m dia class 100D	m	0		Rate Only
22.05	Portal and rectangular culverts:				
	(b) Without prefabricated floor slab				
	(i) 2.4m x 2.4m class 100s rectangular portal culverts	m	20		
22.07	Cast in-situ concrete and formwork				
	(a) In Class A bedding, 75mm screeds and encasing of 1.2m pipes and portal culverts	m³	10		
	(c) Inlet & outlet structures for 1.2m diameter pipes, skewed ends, floor slab, top slabs, approach slabs, wing walls for box culverts and ditch drains excluding formwork but including class U2 surface finish (concrete class 25/19)	m³	60		
CARRIED FORWARD:					

BROUGHT FORWARD:					
ITEM NO.	DESCRIPTION	UNIT	TENDER QTY	RATE	AMOUNT
	(d) Formwork of concrete under sub item 22.07(c) above	m <sup>2</sup>			Rate Only
22.10	Steel reinforcement				
	(b) High-tensile steel bars	t	1.5		
	(c) Welded steel fabric (Ref 888)	m <sup>2</sup>	315		
22.17	Cast in-situ headwalls				
	(i) 600 mm dia	No	8		
	(ii) 900 mm dia	No	2		
B22.30	Backfilling and compaction behind abutments	m <sup>3</sup>	1 200		
TOTAL CARRIED TO SUMMARY					

ITEM NO.	DESCRIPTION	UNIT	TENDER QTY	RATE	AMOUNT
B34.01	<p><b>3400 PAVEMENT LAYERS OF GRAVEL MATERIAL</b></p> <p>Pavement layers constructed from gravel taken from cut or borrow including free haul up to 1.0km</p> <p>(d) Gravel Subbase layer compacted to:</p> <p style="padding-left: 40px;">(i) 93% modified AASHTO density (150mm)</p> <p>(b) Gravel wearing course compacted to</p> <p style="padding-left: 40px;">(ii) Non-cemented material (150mm G5/G6) compacted to 95% Mod AASHTO density</p>	<p>m³</p>                      m³	<p>2 430.0</p>		Rate Only
TOTAL CARRIED TO SUMMARY					